CORPUS CHRSIT REGIONAL TRANSPORATION AUTHORITY

ATTACHMENT A

PRICE SCHEDULE

IFB NO.: 2024-FC-09

VA Clinic Bus Pull In

Instructions:

- (1) Refer to the "General Instructions", "Specifications", and the "Construction Drawings" before completing this Price Schedule and quote your best price.
- (2) This is a 60-calendar day firm-fixed-price construction contract.
- (3) Bidders must provide prices for items 1 through 9. **NO ITEMS MAY REMAIN BLANK.**
- (4) Line item 10 is the Betterment Fund Allowance. It will automatically be calculated into the Total Base Price.
- (5) Unit Prices must be entered in the Price Schedule, and in the case of discrepancy between the unit price and the total price, the unit price will be presumed to be correct.
- (6) The Total Price and the Total Base Price fields are locked and will automatically populate the totals.
- (7) Prices are valid for one hundred twenty (120) calendar days from the Board approval date.
- (8) Submit one signed Price Schedule. On the outside of your sealed Price Schedule address your envelope with the information as noted in Section 5.0 "Submission of Bids" in the "Instructions to Bidders" section in the IFB or submit your Price Schedule electronically to procurement@ccrta.org prior to the deadline.

The undersigned BIDDER proposes and agrees, if this Bid is accepted, to contract with the CCRTA to furnish all work in accordance with the specifications and drawings for this IFB, according to the following unit prices:

BASE BID			
1. 158 LF	DEMOLITION OF EXISTING CURB & GUTTER, (Including demolition and removal, protection of the public), as shown on the plans and as outlined in the specifications, complete in place.		
\$ Unit Price (Figures)			
\$ Total Price (Figures)			
2. 416 SF	DEMOLITION OF EXISTING SIDEWALK, (including demolition, and removal of existing sidewalk protection of the public), as shown on the plans and as outlined in the specifications, complete in place.		
\$ Unit Price (Figures)			
\$ Total Price (Figures)			
3. 168 LF	SAW CUT CONCRETE (FULL DEPTH), as shown on the plans and as outlined in the specifications, complete in place.		
\$ Unit Price (Figures)			
\$ Total Price (Figures)			

IFB NO.: 2024-FC-09

VA Clinic Bus Pull In

FIRM: _____

IFB NO.: 2024-FC-09 VA Clinic Bus Pull In		
4. 300	SF	CONCRETE SHELTER PAD, (including excavation, backfill, bedding, expansion joints, beams, dowels, and reinforcement), as shown on the plans and as outlined in the specifications, complete in place.
\$_ Unit Price	(Figures)	
\$ Total Price	e (Figures)	
5. 1,318	8 SF	8" CONCRETE PAVEMENT, (including excavation, subgrade compaction, limestone base, expansion joints, dowels, and reinforcement, concrete and backfill). The line item shall include the excavation, base and subgrade preparation extending 1' behind the 6" curb, as shown on the plans and as outlined in the specifications, complete in place.
\$_ Unit Price	(Figures)	
\$ Total Price	e (Figures)	
6. 161	LF	6" CURB, (including excavation backfill, bedding, expansion joints, dowels, and reinforcement), as shown on the plans and as outlined in the specifications, complete in place.
\$_ Unit Price	(Figures)	
\$ Total Price	e (Figures)	

FIRM: _____

	VA	Clinic Bu	us Pull In
7.	300	SF	4" CONCRETE SIDEWALK, (including excavation, backfill, bedding, dowels, and reinforcement), as shown on the plans and as outlined in the specifications, complete in place.
\$_ Unit	Price (F	igures)	
\$ Tota	al Price ((Figures)	
8.	1	EA	BUS STOP SIGN, as shown on the plans, complete in place.
\$ Unit	Price (F	igures)	
\$ Tota	al Price ((Figures)	
9.	1	LS	TRAFFIC CONTROL (MOBILIZATION, IMPLEMENTATION AND ADJUSTMENTS), as shown on the plans and as outlined in the specifications, complete in place.
\$ Unit	Price (F	igures)	
\$ Tota	al Price ((Figures)	

IFB NO.: 2024-FC-09

FIRM: _____

			FIRM:
IFB N		24-FC-09 A Clinic Bu	ıs Pull In
10.	1	LS	BETTERMENT FUND ALLOWANCE , as outlined in the specifications.
\$ Unit		5,000.00 Figures)	
\$ Tota	ıl Price	5,000.00 (Figures)	
		ТОТ	AL BASE BID PRICE, Items 1 through 10
\$			
Total	l Price (In Figures)	
			60 CALENDAR DAYS TO COMPLETE THE PERMITTING OT AND THE CONSTRUCTION PROJECT.
Autho	orized	Signatory	:
Signa	iture		Printed Name
Title			Date